



Public Works Department – Engineering Division
(763) 572-3554
August 7, 2020

69th Avenue and Anoka Street Rehabilitation Project

Parking

We ask that you do not park cars on 69th Avenue or Anoka Street in construction areas from 7 a.m. to 7 p.m., Monday-Friday to allow for the contractor to have the space needed to complete the project.

Upcoming Construction

A summary of construction to be expected this upcoming week on 69th Avenue & Anoka Street is as follows (note that dates are subject to changes due to weather, etc.):

Week of August 10:

- Final Preparation for Paving

The contractor will finish work on the street grading to get the street down to the final grade before paving the first lift of asphalt.

- Pave the first (base) lift of asphalt

The contractor will be paving the asphalt base lift on 69th Avenue and Anoka Street.

Please Note:

We ask that you please stay off the new pavement for as long as possible. You will have access to your driveway by the end of the day. This allows for the asphalt to cure and will produce the best final product.

- Raise manholes to final grade

The contractor will cut the pavement and raise the manholes and water valves to their final elevation in preparation for the final lift of asphalt. The manholes are left under the surface of the street and plated over with steel so that the contractor can get proper compaction on the base layers. It also ensures that the manholes are set to the proper final elevation.

- Begin restoration of the project area

The contractor will begin restoring the project area. This includes grading, vegetation, and landscaping.

Upcoming Construction Events

Week of August 17:

- Finish Concrete Work
- Finish Restoration
- Pave final lift of asphalt in streets
- Pave trail section

Week of August 24:

- Pavement Markings
- Signage
- Saw and Seal Streets

Parking

We ask that you do not park cars on 69th Avenue or Anoka Street in construction areas from 7 a.m. to 7 p.m., Monday-Friday to allow for the contractor to have the space needed to complete the project. Street parking causes delays for the contractor and increases the risk of damage to your personal vehicles. Please let us know as soon as possible if you plan on hosting any events (graduation, birthday, holidays, etc.) and we will do our best to work with our contractor to avoid any major inconveniences.

We also ask that you refrain from watering your lawn in areas where if the runoff could go onto the new concrete or gravel road.

Our project engineer, Brandon Brodhag, can be reached at (763) 238-8086 if you have questions.

See the project webpage at fridleymn.gov/projects or contact the City of Fridley Engineering Division at (763) 572-3554 if you need additional information. You may view a project map and sign up for updates to be emailed to you!

